

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of estimate.

	Rs.
1. Cost of constructing a power house as per detailed estimate.	784
2. Cost of rising main and suction pipe	1,911
3. Cost of distribution pipes to main building	2,140
4. Cost of distribution pipes to guests' quarters	165
5. Cost of trial pumping including fitting up the engine and pump.	350
6. Cost of constructing a base for water tank as per estimate ...	1,370
7. Cost of Electric "Motor and Pump"	1,500
8. Cost of Wrought Iron Tank	1,200

NOTE.—Quotations for items 7 and 8 are not to be included as they will be supplied by the Department.

K. SRINIVASAIYENGAR,
Executive Engineer.

MYSORE DIVISION.

Dated 12th June 1912.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 15th July 1912, for restoring Mategere tank, Registered No. 3 of Chamrajnagar Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of April 1914.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Mysore between the hours of 2 and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees five hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Mategere tank, Registered No. 3 of Chamrajnagar Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Southern Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

<i>Description of work</i>			<i>Per</i>	<i>Quantity</i>	<i>Remarks</i>
Bund—					
Earthwork	C. yd.	17,482	
Turfing	S. yd.	10,483	
Old stone work	C. yd.	2,298	
New stone work	"	5,302	
Grade stones with bed stones	No.	64	
Register number stone	"	1	
Bench mark stones	"	2	
Gauge stones	"	1	
Clearing jungle	L. S.	...	will be paid as per actual work done.
Waste weirs—					
Earthwork	C. yd.	2,450	
Brick in surki mortar	C. ft.	5,699	
Plastering in surki mortar	Sqr.	31.14	
Rough stone work new	C. yd.	849	
Do old	"	221	
Clearing site	L. S.	...	Do
Stone slabs 4½" thick	S. ft.	645	
Dismantling old body wall to one uniform level	L. S.	...	Do
Sluices—					
Repairing	L. S.	...	Do

Dated 21st June 1912.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 22nd July 1912, for constructing A. V. School at Heggaddevankote. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1913.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore, between the hours of 2 and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees 300 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing A. V. School at Heggaddevankote," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Southern Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of quantities.

Description of work.	Per unit.	Quantity.
1. Earthwork excavation and filling	C. yd.	111
2. Burnt brick in chunam	C. ft.	10,491
3. Burnt stone slabs, dressed	S. ft.	944
4. Plastering with chunam	Sqr.	99.01
5. White and color-washing	"	99.01
6. Teakwood work wrought and put up	C. ft.	222.83
7. Roofing with 1st class Mangalore tiles, teak reepers, etc. complete	Sqr.	37.07
8. Ridge tiles set in mortar and cement pointed	R. ft.	128
9. Zinc sheets for valleys	S. ft.	140
10. Cut stone pillars, 9" square, with base and capital, 8 feet in height	No.	4
11. Teakwood pannelled doors, complete	S. ft.	224
12. Do do windows with iron bars, etc., complete	"	315
13. Teakwood ventilators, with glazed shutters, iron bars and fan lights	"	204
14. Cornice work over windows and shelves	R. ft.	...
15. Wall shelves	S. ft.	120
16. Chacolate painting	Sqr.	15.34
17. Teakwood ornamental eave board	R. ft.	336
18. Do finials	No.	4
19. Flooring with 9" square Mangalore tiles, laid over 3" concrete and cement pointing...	Sqr.	16.56
20. Flooring with Cudappah slabs over 3" concrete and cement pointing	"	3.83

R. V. SUNDARAM IYER,
Executive Engineer.

SHIMOGA DIVISION.

Dated 26th June 1912.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Shimoga Division, up to 30th July 1912, for improving the Government house at Shimoga. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of February 1913.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Shimoga between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.